

## Consent

---

**From:** Consent  
**Sent:** Thursday, March 28, 2024 1:21 PM  
**To:** sromumbai4@mpcb.gov.in  
**Subject:** Submission of Half Yearly Post Monitoring Report for the period of October, 2022 – March, 2023 for the Residential Project “City of Joy” of Village Mulund (W), Mumbai- 400080, Maharashtra. M/s. Nirmal Lifestyle (India) Pvt. Ltd  
**Attachments:** PMR\_CITY OF JOY\_ Oct,22 - Mar,23.pdf

To,  
The SRO Mumbai - IV ,  
M.P.C.Board,  
Kalapataru point, Sion (East),  
Mumbai – 400 022.  
Maharashtra

Subject: Submission of Half Yearly Post Monitoring Report for the period of October, 2022 – March, 2023 for the Residential Project “City of Joy” at new C.T.S. Nos. 661/1/4, 661/1/5, 661/1/6, 661/1/7 & 661/8 of Village Mulund (W), Mumbai- 400080, Maharashtra.

Reference: Clearance letter no. SEAC- 2014/CR- 438 /TC-1 dtd. 03.09.2014.

Dear Sir,

This is with reference to the above subject for our project. We are submitting herewith our half yearly monitoring report with following contents:

- Data Sheet.
- Compliance Report.
- Post monitoring report.
- Energy conservation report.
- Copy of Environmental Clearance.
- Copy of Consent to Establish.
- Copies of the advertisement published in the newspaper (Marathi & English).

This is for your kind information.

Thanking you,

Yours truly,

**M/s. Nirmal Lifestyle (India) Pvt. Ltd**

C.C TO: 1. The Director, MoEF&CC, Nagpur.  
2. The Secretary, Environment Department, Mantralaya, Mumbai



Thanks & Regards

**Dwirukti Poddar**

M/s. Enviro Analysts and Engineers Private Limited.

B-1003, Enviro House, 10th floor.

Western Edge-II, W.E Highway.

Borivali(E), Mumbai-400066

Mobile No: 9322086202

Tel No: 91-22 2854 1647/48/49/67/68

Email: consent@eaepl.com / d.poddar@eaepl.com

“File this email in an email folder and save a tree.”

## Consent

---

**From:** Consent  
**Sent:** Thursday, March 28, 2024 1:21 PM  
**To:** eccompliance-mh@gov.in  
**Subject:** Submission of Half Yearly Post Monitoring Report for the period of October, 2022 – March, 2023 for the Residential Project “City of Joy” of Village Mulund (W), Mumbai- 400080, Maharashtra. M/s. Nirmal Lifestyle (India) Pvt. Ltd  
**Attachments:** PMR\_CITY OF JOY\_ Oct,22 - Mar,23.pdf

To,  
**The Director**  
**Ministry of Environment, Forests & Climate Change,**  
Regional Office, West Central Zone,  
New Secretarial Building, East wing, Civil Lane,  
Near Old VCA stadium,  
**Nagpur - 440001.**  
**Maharashtra.**

Subject: Submission of Half Yearly Post Monitoring Report for the period of October, 2022 – March, 2023 for the Residential Project “City of Joy” at new C.T.S. Nos. 661/1/4, 661/1/5, 661/1/6, 661/1/7 & 661/8 of Village Mulund (W), Mumbai- 400080, Maharashtra.

Reference: Clearance letter no. SEAC- 2014/CR- 438 /TC-1 dtd. 03.09.2014.

Dear Sir,

This is with reference to the above subject for our project. We are submitting herewith our half yearly monitoring report with following contents:

- Data Sheet.
- Compliance Report.
- Post monitoring report.
- Energy conservation report.
- Copy of Environmental Clearance.
- Copy of Consent to Establish.
- Copies of the advertisement published in the newspaper (Marathi & English).

This is for your kind information.

Thanking you,

Yours truly,

**M/s. Nirmal Lifestyle (India) Pvt. Ltd**

C.C TO: 1. Environment Department, Mantralaya, Mumbai.  
2. M.S., MPCB, Mumbai.



Thanks & Regards

*Dwirukti Poddar*

M/s. Enviro Analysts and Engineers Private Limited.

B-1003, Enviro House, 10th floor.

Western Edge-II, W.E Highway.

Borivali(E), Mumbai-400066

Mobile No: 9322086202

Tel No: 91-22 2854 1647/48/49/67/68

Email: [consent@eaepl.com](mailto:consent@eaepl.com) / [d.poddar@eaepl.com](mailto:d.poddar@eaepl.com)

“File this email in an email folder and save a tree.”



Date: 28.03.2024

To,  
The Director  
Ministry of Environment, Forests & Climate Change,  
Regional Office, West Central Zone,  
New Secretarial Building, East wing, Civil Lane,  
Near Old VCA stadium,  
Nagpur - 440001.  
Maharashtra.

Subject: Submission of Half Yearly Post Monitoring Report for the period of October 2022 – March 2023 for the Residential Project “City of Joy” at new C.T.S. Nos. 661/1/4, 661/1/5, 661/1/6, 661/1/7 & 661/1/8 of Village Mulund (W), Mumbai- 400080, Maharashtra.

Reference: Clearance letter no. SEAC- 2014/CR- 438 /TC-1 dtd. 03.09.2014.

Dear Sir,

This is with reference to the above subject for our project. We are submitting herewith our half yearly monitoring report with following contents:

- Data Sheet.
- Compliance Report.
- Post monitoring report.
- Energy conservation report.
- Copy of Environmental Clearance.
- Copy of Consent to Establish.
- Copies of the advertisement published in the newspaper (Marathi & English).

This is for your kind information.

Thanking you,

Yours truly,  
M/s. Nirmal Lifestyle Ltd.

Authorized Signatory



C.C TO: 1. Environment Department, Mantralaya, Mumbai.  
2. M.S., MPCB, Mumbai.

Our Proud Associations:



Date: 28.03.2024

To,

**The Director**  
**Ministry of Environment, Forests & Climate Change,**  
 Regional Office, West Central Zone,  
 New Secretarial Building, East wing, Civil Lane,  
 Near Old VCA stadium,  
**Nagpur - 440001.**  
**Maharashtra.**

**Subject : Present status of Project work for the period of October, 2022 – March, 2023.**

**Reference : Clearance letter no. SEAC- 2014/CR- 438 /TC-1 dtd. 03.09.2014.**

Dear Sir,

This is with reference to the above subject, our Residential Project “City of Joy” at new C.T.S. Nos. 661/1/4, 661/1/5, 661/1/6, 661/1/7 & 661/8 of Village Mulund (W), Mumbai- 400080, Maharashtra.

The present project status at site is as follows :

Building	Wings	Floors	Status
Building – 5	B	P1+P2+Stilt+20 Floors	Internal finishing work up to 20 <sup>th</sup> Floor
Building – 6	A	B+P1+P2+Stilt+36 Floors.	R.C.C Slabs Completed upto 32nd Floor
	B	B+P1+P2+Stilt+36 Floors.	R.C.C Slabs Completed upto 32nd Floor
Building -9	A	B1+B2+P1 to P3+Stilt+40 Floors.	RCC Slabs Completed upto 19 <sup>th</sup> Floors.
	B	B1+B2+P1 to P3+Stilt+40 Floors.	RCC Slabs Completed upto 19 <sup>th</sup> Floors.
	C	B1+B2+P1 to P3+Stilt+40 Floors.	Construction not started.
	D	B1+B2+P1 to P3+Stilt+40 Floors.	RCC Slabs Completed upto 1 <sup>st</sup> Floors
	E	B1+B2+P1 to P3+Stilt+40 Floors.	RCC Slabs Completed upto 1 <sup>st</sup> Floors

Thanking you,

Yours truly,  
**M/s. Nirmal Lifestyle Ltd.**

Authorized Signatory



Our Proud Associations:



# **DATA SHEET**

Developer

**M/s. Nirmal Lifestyle Pvt. Ltd.**

NEW C.T.S. Nos 66111/4,661/1/5,661/1/6,  
661\1\7 & 661/8 of Village Mulund (W), Mumbai-400 080

**MONITORING THE IMPLEMENTATION OF ENVIRONMENTAL SAFEGUARDS**

Ministry of Environmental and Forests  
Regional Office, West Central Zone, Nagpur.  
Monitoring Report

**PART – I****DATA SHEET**

1.	Project type: river-valley/ mining/ Industry/thermal/ nuclear/ Other (specify)	Residential building
2.	Name of the project	"City of Joy"
3.	Clearance letter (s) / OM/ no and date:	File No.: SEAC-2014/CR-438/TC- I dtd. 03.09.2014 File No . 21- 1007 /2007 -IA .III dtd 26.08.2008
4.	Location	NEW C.T.S. Nos 66111/4,661/1/5,661/1/6, 661\1\7 & 661/8 of Village Mulund (W), Mumbai-400 080, Maharashtra.
a.	District (s)	Mumbai
b.	State (s)	Maharashtra
c.	Latitude / Longitude	-
5.	Address for correspondence	
a.	Address of concerned project Chief Engineer (with pin code & telephone / telex / fax numbers)	Mr Dinesh Changlani , Address: Godrej One, 5th floor, Pirojshanagar, Eastern Express Highway, Vikhroli (E), Mumbai - 400 079, Tel. : 022-61698500, Fax : 022-61698888
b.	Address of Executive Project Engineer /Manager (with pin code / fax number)	Mr Dinesh Changlani , Address: Godrej One, 5th floor, Pirojshanagar, Eastern Express Highway, Vikhroli (E), Mumbai - 400 079, Tel. : 022-61698500, Fax : 022-61698888

6.	Salient features	
a.	of the project	Total Plot Area: 80371.92sqm. FSI Area: 56,793.77 sqm. Non- FSI Area: 70,871.73 sqm. Total Construction Area: 147543.31 sq. m
b.	of the environmental management plans	1. Sewage Treatment Plant: Sewage Treatment Plant Of 660 KLD will be provided for treating the wastewater. Recycled wastewater will be used for Flushing, gardening etc. 2. Water Management: Rain Water Harvesting shall be provided to raise the ground water table. 3. Solid Waste Management: Solid waste to be segregated at source and handed over to authorized local vendor for further disposal.
7.	Break Up Of the project Area	
a.	Submerge area: forest & non-forest	Non-Forest

b.	Others	Total Plot Area: 80371.92sqm. FSI Area: 56,793.77 sqm. Non- FSI Area: 70,871.73 sqm. Total Construction Area: 147543.31 sq. m
8.	Breakup of the project affected: Population with enumeration of those losing houses / dwelling units, only agriculture land only, both dwelling units and agriculture land and landless labourers/artisan.	No any.
a.	SC, ST / Adivasis	---
b.	Others	---
	(Please indicate whether these figures are based on any scientific and systematic survey carried out or only provisional figures, if a survey is carried out give details and years of survey).	---
9.	Financial details	
a.	Project cost as originally planned and subsequent revised estimates and the year of price reference	Total cost: 140 Crores
b.	Allocation made for environmental management plans with item wise and year wise break-up	EMP Cost: ➤ Capital Cost- 279.4 Lacs ➤ O & M Cost- 18.32 Lacs/Yr
c.	Benefit cost ratio/ Internal rate of return and the year of assessment	
d.	Whether (c) includes the cost of environmental management as shown in the above	
e.	Actual expenditure incurred on the project so far	85.44 cr

f.	Actual expenditure incurred on the environmental management plans so far	NIL
10.	Forest land required	
a.	The status of approval for diversion of forest land for non-forestry use	The land is of non-forest type hence not applicable.
b.	The status of clearing and felling	Total RG area - RG area on Ground: 22380.83 sq.mt. A combination of native evergreen trees and ornamental flowering trees, shrubs and palms are planned in the complex. There will be tree plantation of different species selected as per CPCB green belt guidelines and common species available in the proposed area.
c.	The status of compensatory afforestation, if any	---
d.	Comments on the viability & sustainability of compensatory afforestation program in the light of actual field experience so far	N.A.
11.	The status of clear felling in non-forest areas (such as submergence area of reservoir, approach roads), if any with quantitative information	N.A.
12.	Status of construction	
a.	Date of commencement (Actual and/or planned)	September,2009
b.	Date of completion (Actual and/ of planned)	31/03/26
13.	Reasons for the delay if the project is yet to start	---
14.	Dates of site visits	
a.	The date on which the project was monitored by the regional office on previous occasions, if any	Not yet monitored.
b.	Date of site visit for this monitoring report	17.11.2022; 28.02.2023
15.	Details of correspondence with project authorities for obtaining action plans/ information on status on compliance to	File No.: SEAC-2014/CR-438/TC- I dtd. 03.09.2014 File No . 21- 1007 /2007 -IA .III dtd 26.08.2008

	safeguards other than the routine letters for logistic support for site visits	M/s Nirmal Lifestyle (India) Pvt. Ltd Regd. Office: Nirmal Ltd, Nirmal Mall, 3rd Floor, Multiplex Building, L.B.S. Marg, Opp. Nirmal Nagar, Mulund (W), Mumbai 80.
--	--	---



# **COMPLIANCE REPORT**

Developer

**M/s. Nirmal Lifestyle Pvt. Ltd.**

NEW C.T.S. Nos 66111/4,661/1/5,661/1/6,  
661\1\7 & 661/8 of Village Mulund (W), Mumbai-400 080

# COMPLIANCE REPORT

## PART A- SPECIFIC CONDITIONS:

### I. Construction Phase:

1.	This environment clearance is issued subject to restricting total no of new flats to be constructed up to 738 as approved by the local authority. PP may approach to SEIAA as and when local authority approves the proposed new flats.	PP is agreeable to the same.
2.	This environmental clearance is issued subject to land use verification. Local authority / planning authority should ensure this with respect to Rules, Regulations, Notifications, Government Resolutions, Circulars, etc. issued if any. Judgments/orders issued by Hon'ble High Court, Hon'ble NOT, Hon'ble Supreme Court regarding OCR provisions, environmental issues applicable in this matter should be verified. PP should submit exactly the same plans appraised by concern SEAC and SEIAA. If any discrepancy found in the plans submitted or details provided in the above para may be reported to environment department. This environmental clearance issued with respect to the environmental consideration and it does not mean that State Level Impact Assessment Authority (SEIAA) approved the proposed land use.	PP is agreeable to the same.
3.	This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.	PP is agreeable to the same.
4.	PP has to abide by the conditions stipulated by SEAC & SEIAA.	PP is agreeable to the same.

5.	The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.	PP is agreeable to the condition.
6.	"Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.	PP is agreeable to the condition.
7.	All required sanitary and hygienic measure should be in place before starting construction activities and to be maintained throughout the construction phase.	All required sanitary and hygienic measure will be in place before starting construction activities and to be maintained throughout the construction phase.
8.	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.	PP is agreeable to the condition.
9.	Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, creche and First Aid Room etc.	Provision will be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, creche and First Aid Room etc.
10.	Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.	PP is agreeable to the condition.
11.	The solid waste generated should be properly collected and segregated. dry/inert solid waste	The solid waste generated will be properly collected and segregated. dry/inert solid waste

	should be disposed off to the approved sites for land filling after recovering recyclable material	should be disposed off to the approved sites for land filling after recovering recyclable material
12.	Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.	Wet garbage will be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority ensure this.
13.	Arrangement shall be made that waste water and storm water do not get mixed.	Arrangement will be made that waste water and storm water do not get mixed.
14.	All the topsoil excavated during construction activities should be stored for use in horticulture/landscape development within the project site.	All the topsoil excavated during construction activities will be stored for use in horticulture/landscape development within the project site.
15.	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.	Additional soil for leveling of the proposed site will be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
16.	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.	Green Belt Development will be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
17.	Disposal of muck during construction phase shall not create any adverse effect on the neighboring communities and be disposal taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.	All construction waste will gets collected and segregated properly. Most of that will be reused for the construction activity. Muck will be dried before its final disposal.
18.	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
19.	Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water.	Construction spoils, including bituminous material and other hazardous materials, will not be allowed to contaminate watercourses and the dump sites for such material will be secured so that they should not leach into the ground water.

20.	Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.	Hazardous waste generated during construction phase will be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board
21.	The diesel generator sets to be used during construction phase shall be low sulphur diesel type and shall conform to Environmental (Protection) prescribed for air and noise emission standard.	DG sets which will be used for backup during construction phase. These are environment friendly make and provided with acoustic enclosure to avoid noise emission.
22.	The diesel required for operating DG sets shall be stored In underground tanks and clearance from Chief Controller of Explosives shall be taken, as applicable.	The diesel required for operating DG sets will be stored In underground tanks and clearance from Chief Controller of Explosives will be taken, as applicable
23.	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.	The PUC checked/authorized vehicles are allowed on the site for transfer of material.
24.	Ambient noise levels should conform to residential standards both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/ SPCB.	During construction, phase adequate measures will be maintain the prescribed limits. Ambient air & Noise level monitoring is being carried out during construction phase. Monitoring reports for Air & Noise are attached.
25.	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003.	Fly ash will be used as building material in the construction as per the provisions of Fly Ash Notification of September, 1999 and amended as on 27th August, 2003.
26.	Ready mixed concrete must be used in building construction.	Ready mixed concrete will be used in building construction.
27.	The approval of competent authority shall be obtained for structural safety of the buildings due to any possible earthquake, adequacy of fire fighting equipments etc. as per National Building Code including measures from lighting.	The approval of competent authority will be obtained for structural safety of the buildings due to any possible earthquake, adequacy of fire fighting equipments etc. as per National Building Code including measures from lighting.
28.	Storm water control and its re-use as per CGWB and BIS standards for various applications.	Storm water will be control and its re-use as per CGWB and BIS standards for various

		applications.
29.	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.	Water demand during construction will be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
30.	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.	The ground water level and its quality will be monitored regularly in consultation with Ground Water Authority.

31.	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.	Condition noted by PP.
32.	Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.	Condition noted by PP.
33.	Permission to draw ground water shall be obtained from the competent Authority prior to construction/ operation of the project.	Condition noted by PP.
34.	Separation of grey and black water should be done by the use of dual plumbing line for separation of grey and black water.	Yes, water will be separated by the use of dual plumbing line.
35.	Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.	Fixtures for showers, toilet flushing and drinking will be of low flow either by use of aerators or pressure reducing devices or sensor based control.
36.	Use of glass may be reduced by up-to 40% to reduce the electricity consumption and load on air-conditioning. If necessary, use high quality double glass with special reflective coating in windows.	Use of glass will be reduced by up-to 40% to reduce the electricity consumption and load on air-conditioning. If necessary, use high quality double glass with special reflective coating in windows

37.	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement	Condition noted.
38.	Energy conservation measures like installation of CFL's/LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning. Used CFL's, TFL and LED shall be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination.	A separate sheet of energy conservation is attached with this report.
39.	Diesel power generating sets proposed as source of back-up power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board.	Condition is noted.
40.	Noise should be controlled to ensure that it does not exceed the prescribed standards. During night time the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.	Condition is noted.
41.	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.	Condition is noted.
42.	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspirational for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement	Condition is noted.
43.	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation,	Condition is noted.

44.	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.	Condition is noted.
45.	Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.	Condition is noted.
46.	Six monthly monitoring reports should be submitted to the Regional office MoEF, Bhopal with copy to this department and MPCB.	Condition is noted.
47.	A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.	Condition is noted.
48.	In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this ministry.	Condition is noted.
49.	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.	Condition is noted.
50.	Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.	Condition is noted.
51.	The project proponent shall advertise at least in two local newspapers widely circulated in the region, one of which shall be in the vernacular language informing that the project has been accorded Environmental Clearance and copies of clearance letter are available with the State Pollution Control Board and may also be seen at Website of the Ministry of Environment, Forest and Climate Change at <a href="http://www.envfor.nic.in">http://www.envfor.nic.in</a> . The advertisement shall be made within Seven days from the date of receipt of Clearance letter and a copy of the same shall be forwarded to the Regional office of this Ministry at Nagpur.	Condition is noted.



52.	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1 <sup>st</sup> June & 1 <sup>st</sup> December of each calendar year,	Condition is noted.
53.	A copy of the clearance letter shall be sent by proponent to the concerned Panchayat, Zilla Parisad/ Municipal Corporation, Urban local Body and the Local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.	The PP comply the condition.
54.	The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF&CC the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels mainly; SPM, RSPM, SO <sub>2</sub> , NO <sub>x</sub> (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.	Condition is noted.
55.	The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.	Condition is noted.
56.	The environmental statement for each financial year ending 31 <sup>st</sup> March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.	Condition is noted.
57.	The environmental clearance is being issued without prejudice to the action initiated under EP	Condition is noted.

	Act or any comt case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.	
58.	In case of submission of false document and non compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environmental Clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.	Condition is noted.
59.	The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.	Condition is noted.
60.	Validity of Environment Clearance: The environmental clearance accorded shall be valid for a period of 5 years.	Condition is noted.
61.	In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.	Condition is noted.
62.	These stipulations would be enforced among others under the provisions of the water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and the EIA Notification, 2006.	Condition is noted.
63.	Any appeal against this clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.	Condition is noted.

# **ENERGY CONSERVATION MEASURES**

Developer

**M/s. Nirmal Lifestyle Pvt. Ltd.**

NEW C.T.S. Nos 66111/4,661/1/5,661/1/6,  
661\1\7 & 661/8 of Village Mulund (W), Mumbai-400 080

## **ENERGY CONSERVATION MEASURES**

<b>ENERGY SAVING SUMMARY FOR BUILDING NO 5B</b>			
<b>Sr.No</b>	<b>Items</b>	<b>Total Elect. Load- Conventional case (Kw)</b>	<b>Elect. demand after using Energy saving means (kw)</b>
	Energy Saving Parameters		
1	Stilt & Refuge area Ltg	6	3.7
2	External Area Ltg.	5	3.3
3	Common Area Ltg	6	3.5
4	Lifts - with VFD & Regenerative Type	65	59
5	Plumbing System Load	19	17
	Total	100	86
<b>Overall Saving for the Project in %</b>			<b>14</b>
<b>Total Units saved based on Unit Consumption - (Kw)</b>			<b>14</b>
<b>ENERGY SAVING SUMMARY FOR BUILDING NO 6</b>			
<b>Sr.No</b>	<b>Items</b>	<b>Total Elect. Load- Conventional case (Kw)</b>	<b>Elect. demand after using Energy saving means (kw)</b>
	Energy Saving Parameters		
1	Basement	25	17
2	Stilt, Podium & Refuge Floor	13.5	9
3	External Area Ltg.	8	5
4	Common Area Ltg	13	8
5	Lifts - with VFD & Regenerative Type	200	180
6	Plumbing System Load	35	32
8	Basement Ventilation	150	135

9	Solar Lighting ( 40% of common area ltg)	8	0
	Total	453	385
<b>Overall Saving for the Project in %</b>			<b>15</b>
<b>Total Units saved based on Unit Consumption - (Kw)</b>			<b>68</b>

<b>ENERGY SAVING SUMMARY FOR BUILDING NO 9</b>			
<b>Sr.No</b>	<b>Items</b>	<b>Total Elect. Load- Conventional case (Kw)</b>	<b>Elect. demand after using Energy saving means (kw)</b>
	Energy Saving Parameters		
1	Basement	40	26
2	Stilt & Podium Floor	43	28
3	External Area Ltg.	10	7
4	Common Area Ltg	37	22
5	Lifts - with VFD & Regenerative Type	548	493
6	Plumbing System Load	112	101
8	Basement Ventilation	500	450
9	Shaft Ventilation	100	90
10	Solar Lighting ( 40% of common area ltg)	24	0
	Total	1,414	1,217
<b>Overall Saving for the Project in %</b>			<b>14</b>
<b>Total Units saved based on Unit Consumption - (Kw)</b>			<b>197</b>

**HALF YEARLY POST ENVIRONMENTAL  
MONITORING REPORT**

OF

**Residential Project "CITY OF JOY"**

For

**October, 2022 – March, 2023**

Developer

**M/s. Nirmal Lifestyle Pvt. Ltd.**

NEW C.T.S. Nos 66111/4,661/1/5,661/1/6,  
661\1\7 & 661/8 of Village Mulund (W), Mumbai-400 080

Prepared by

**ENVIRO ANALYSTS & ENGINEERS P. LTD.,**

## Ambient Air Quality Monitoring Report

<b>Report No. - EAEPL/A/11/22/01253</b>		<b>Report Date - 25.11.2022</b>	
<b>Name of Customer</b>	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Ambient Air	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/A/11/22/01253 (Near Main Gate of Site)	<b>Sample quantity and packing</b>	PM <sub>10</sub> = 1 * 1 No. Filter paper. PM <sub>2.5</sub> = 1 * 1 No. Filter paper. SO <sub>x</sub> = 30ml * 2 No. PVC bottle. NO <sub>x</sub> = 30ml * 2 No. PVC bottle.
		<b>Sample Preservation</b>	Filter papers – Transported and stored in desiccator. PVC bottles - Transported and stored at 5°C (±1 °C).
<b>Date of Sampling</b>	17.11.2022	<b>Date of Receipt</b>	18.11.2022
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/01		
<b>Period of Analysis</b>	18.11.2022 to 19.11.2022		
<b>Report for the month</b>	November, 2022		

Discipline: Chemical

Group: Atmospheric Pollution

Environmental Conditions			
Ambient Air Temperature (°C)	Relative Humidity (%)	Duration of Monitoring	
32°C	65 %	8 hours	
RESULTS			
Tests Parameter	Results	NAAQS LIMITS	METHOD
R.S.P.M (PM <sub>10</sub> ) (µg/m <sup>3</sup> )	82.10	100 µg/m <sup>3</sup>	IS 5182 (Part 23) 2006 Reaffirmed 2017
R.S.P.M (PM <sub>2.5</sub> ) (µg/m <sup>3</sup> )	47.49	60 µg/m <sup>3</sup>	IS 5182 (Part 24) 2019
SO <sub>2</sub> (µg/m <sup>3</sup> )	24.11	80 µg/m <sup>3</sup>	IS 5182 Part-2 (2001) Reaffirmed 2017
NO <sub>x</sub> (µg/m <sup>3</sup> )	29.73	80 µg/m <sup>3</sup>	IS 5182 Part-6 (2006) Reaffirmed 2017

**Remark:** All the measured values are within NAAQS limits.

-----End-----

For M/s. ENVIRO ANALYSTS & ENGINEERS PVT. LTD.,

**Authorized Signatory**  
(Netra Pawar)

- Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.



## Water Sample Analysis Report

<b>Report No. - EAEPL/W/11/22/01254</b>		<b>Report Date – 25.11.2022</b>		
<b>Name of Customer</b>	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019	
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.			
<b>Nature and Description of Sample</b>	Tanker Water	<b>Sample Collected by</b>	EAEPL Laboratory	
<b>Sampling Locations and Sample Code</b>	EAEPL/W/11/22/01254 (Near Site office)	<b>Sample Quantity and Packing</b>	2 L X 1 No. PVC Can.	
<b>Date of Sampling</b>		17.11.2022	<b>Sample Preservation</b>	Cool -Transported and stored at 5 °C (± 1°C).
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/02		<b>Date of Receipt</b>	18.11.2022
<b>Period of Analysis</b>	18.11.2022 to 25.11.2022			
<b>Report for the month</b>	November, 2022			

Discipline: Chemical

Group: Water

Parameters	Unit	Results	Method
pH	-	8.20	IS 3025 (Part 11) 2022
Total Dissolved Solids	mg / L	336.00	IS 3025 (Part 16) (1984) Reaffirmed 2017
Alkalinity	mg / L	283.25	IS 3025 (Part 23) (1986) Reaffirmed 2019
Turbidity	NTU	< 1.00	IS 3025 (Part 10) (1984) Reaffirmed 2017
Chlorides as Cl	mg / L	69.96	IS 3025 (Part 32) (1988) Reaffirmed 2019
Total Hardness	mg / L	237.70	IS 3025 (Part 21) (2009) Reaffirmed 2019
Calcium	mg / L	54.51	IS 3025 (Part 40) (1991) Reaffirmed 2019
Residual chlorine	mg / L	ND	IS 3025 (Part 26) 2021
Sulphate	mg / L	16.68	IS 3025 (Part 24) Sec1:2022
Nitrate	mg / L	ND	APHA 4500 NO <sub>3</sub> -B (23 <sup>rd</sup> Edition)
Fluoride	mg / L	ND	APHA 4500 F-D (23 <sup>rd</sup> Edition)
<b>Heavy Metals:</b>			
Iron (Fe)	mg / L	ND	IS 3025 (Part 2) 2019
Copper (Cu)	mg / L	ND	IS 3025 (Part 2) 2019
Zinc (Zn)	mg / L	ND	IS 3025 (Part 2) 2019
Lead (Pb)	mg / L	ND	IS 3025 (Part 2) 2019
Chromium (Cr)	mg / L	ND	IS 3025 (Part 2) 2019

Note: ND – Not Detected

End

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,

 Authorized Signatory  
(Netra Pawar)

- Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.



## Water Sample Analysis Report

Report No. - EAEPL/W/11/22/01254		Report Date - 25.11.2022	
Name of Customer	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		Reference – WO # RA/WO/007/2019 Dated 18.10.2019
Site Address	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
Nature and Description of Sample	Tanker Water	Sample Collected by	EAEPL Laboratory
Sampling Locations and Sample Code	EAEPL/W/11/22/01254 (Near Site office)	Sample Quantity and Packing	250ml X 1 No. St. PP Bottle
		Sample Preservation	Cool -Transported and stored at 5°C (± 1°C).
Date of Sampling	17.11.2022	Date of Receipt	18.11.2022
Sampling Procedure	EAEPL/LAB/MB/SOP/17		
Period of Analysis	18.11.2022 to 23.11.2022		
Report for the month	November, 2022		


Discipline: Biological

Group: Water

Parameters	Unit	Results	Method
<b>Microbiological Analysis:</b>			
Coliforms	MPN/100ml	1600	IS 1622:(1981) Reaffirmed 2019
<i>E. coli</i>	MPN/100ml	< 2	IS 1622:(1981) Reaffirmed 2019

End

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,



Authorized Signatory  
(Shweta Sonawane)

- Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.

## Soil Sample Analysis Report

<b>Report No. - EAEPL/S/11/22/01255</b>		<b>Report Date - 25.11.2022</b>
<b>Name of Customer</b>	<b>M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"</b>	<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.	
<b>Nature and Description of Sample</b>	Soil	<b>Sample Collected by</b> EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/S/11/22/01255 (Centreside of Site)	<b>Sample quantity and packing</b>
		500 gm X 1 zip lock bag
<b>Date of Sampling</b>	17.11.2022	<b>Preservation</b> Transported & stored in dry area
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/03	<b>Date of Receipt</b> 18.11.2022
<b>Period of Analysis</b>	18.11.2022 to 25.11.2022	
<b>Report for the month</b>	November, 2022	

Discipline: Chemical

Group: Soil &amp; Rock

Parameters	Unit	Results	Methods
pH	-	7.68	IS 2720 (Part 26):1987, Reaffirmed:2021
Electrical Conductivity	µS/cm	384.00	IS 14767:2000, Reaffirmed:2021
Organic Matter	%	2.60	IS 2720 (Part 22) – 1972 (Reaffirmed 2020)
Available Phosphorus	mg/kg	1.80	EAEPL/LAB/SOP/SOIL/11
Sulphate	mg/kg	32.48	IS 2720 (Part 27) 1977 Reaffirmed 2020
Soil Moisture	%	18.38	IS 2720 (Part 02):1973 (Reaffirmed 2020) Oven drying method
Water Holding Capacity	%	38.562	EAEPL/LAB/SOP/SOIL/10
Total Kjeldhal Nitrogen	mg/kg	835.96	IS 14684:1999 (Reaffirmed 2019)
Calcium	mg/kg	2210.41	EPA 9080
Magnesium	mg/kg	113.80	EPA 9080
Chlorides	mg/kg	106.40	EAEPL/LAB/SOP/SOIL/03
Sodium (Na)	mg/kg	925.60	EPA 3050B
Potassium (K)	mg/kg	557.15	EPA 3050B
<b>Heavy Metals:</b>			
Iron	mg/kg	35352.26	EPA 3050B
Lead	mg/kg	7.19	EPA 3050B
Copper	mg/kg	47.63	EPA 3050B
Zinc	mg/kg	35.05	EPA 3050B

End-----

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,



**Authorized Signatory**  
(Netra Pawar)

Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.



## Ambient Noise Level Monitoring Report

<b>Report No. - EAEPL/N/11/22/01256</b>		<b>Report Date - 25.11.2022</b>	
<b>Name of Customer</b>	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Noise	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/N/11/22/01256	<b>Sample quantity and packing</b>	Not Applicable
<b>Date of Sampling</b>	17.11.2022	<b>Date of Receipt</b>	Not Applicable
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/04		
<b>Period of Analysis</b>	Not Applicable		
<b>Report for the month</b>	November, 2022		

Discipline: Chemical


Group: Atmospheric Pollution

Monitoring Locations	Units	Results		CPCB Norms	
		Day Time	Night Time	Day	Night
Near Main Gate of Site	dB(A) Leq.	54.7	44.3	55	45
Near Backside of Site	dB(A) Leq.	51.3	40.1	55	45
Near Site office	dB(A) Leq.	53.6	43.1	55	45
Near Centreside of site	dB(A) Leq.	52.4	41.3	55	45

**Remark:** The noise level was observed to be within CPCB limit at all of the location.

-----End-----

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,

  
 Authorized Signatory  
 (Netra Pawar)

Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).

2. This report is not to be reproduced except in full, without written approval of the laboratory.

## Ambient Air Quality Monitoring Report

<b>Report No - EAEPL/A/02/23/00278A</b>		<b>Report Date – 08.03.2023</b>	
<b>Name of Customer</b>	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Ambient Air	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/A/02/23/00278A (Near Main Gate of Site)	<b>Sample quantity and packing</b>	PM <sub>10</sub> = 1 * 1 No. Filter paper. PM <sub>2.5</sub> = 1 * 1 No. Filter paper. SO <sub>2</sub> = 30ml * 2 No. PVC bottle. NO <sub>2</sub> = 30ml * 2 No. PVC bottle.
		<b>Preservation</b>	Filter papers – Transported and stored in desiccators. PVC bottles - Transported and stored at 5°C (±1 °C).
<b>Date of Sampling</b>	28.02.2023	<b>Date of Receipt</b>	01.03.2023
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/01		
<b>Period of Analysis</b>	01.03.2023 to 02.03.2023		
<b>Report for the month</b>	February, 2023		

Discipline: Chemical

Group: Atmospheric Pollution

Environmental Conditions			
Ambient Air Temperature (°C)	Relative Humidity (%)	Duration of Monitoring	
31°C	66%	8 hours	
RESULTS			
Tests Parameter	Results	NAAQS LIMITS	METHOD
Particulate Matter (PM <sub>10</sub> )	82.16	100 µg/m <sup>3</sup>	IS 5182 (Part 23) 2006 Reaffirmed 2017
Particulate Matter (PM <sub>2.5</sub> )	42.49	60 µg/m <sup>3</sup>	IS 5182 (Part 24) 2019
Sulphur Dioxide (SO <sub>2</sub> )	21.43	80 µg/m <sup>3</sup>	IS 5182 (Part-2) 2001 Reaffirmed 2017
Nitrogen Dioxide (NO <sub>2</sub> )	23.68	80 µg/m <sup>3</sup>	IS 5182 (Part -6) 2006 Reaffirmed 2017

**Remark:** All the measured values are within NAAQS limits.

-----End-----

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,



**Authorized Signatory**  
(Netra Pawar)

Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.



## Water Sample Analysis Report

<b>Report No - EAEPL/W/02/23/00278B</b>		<b>Report Date – 08.03.2023</b>	
<b>Name of Customer</b>	<b>M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"</b>		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Tanker Water	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/W/02/23/00278B (Near Site Office)	<b>Sample quantity and packing</b>	2 L X 1 No. PVC Can.
		<b>Preservation</b>	Cool -Transported and stored at 5°C (± 1°C).
<b>Date of Sampling</b>	28.02.2023	<b>Date of Receipt</b>	01.03.2023
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/02		
<b>Period of Analysis</b>	01.03.2023 to 08.03.2023		
<b>Report for the month</b>	February, 2023		

Discipline: Chemical

Group: Water

Parameters	Unit	Results	Method
pH	-	7.81	IS 3025 (Part 11) 2022
Total Dissolved Solid	mg / l	292.00	IS 3025 (Part 16) (1984) Reaffirmed 2017
Turbidity	NTU	< 1.00	IS 3025 (Part 10) (1984) Reaffirmed 2017
Alkalinity	mg / l	177.65	IS 3025 (Part 23) (1986) Reaffirmed 2019
Chlorides as Cl	mg / l	42.38	IS 3025 (Part 32) (1988) Reaffirmed 2019
Total Hardness	mg / l	203.56	IS 3025 (Part 21) (2009) Reaffirmed 2019
Calcium	mg / l	48.10	IS 3025 (Part 40) (1991) Reaffirmed 2019
Residual chlorine	mg / l	ND	IS 3025 (Part 26) 2021
Sulphate	mg / l	24.15	IS 3025 (Part 24) Sec1:2022
Nitrate	mg / l	ND	APHA 4500 NO <sub>3</sub> -B(23 <sup>rd</sup> edition)
Fluoride	mg / l	ND	APHA 4500 F-D(23 <sup>rd</sup> edition)
<b>Heavy Metals:</b>			
Iron (Fe)	mg / l	ND	IS 3025 (Part 2) 2019
Copper (Cu)	mg / l	ND	IS 3025 (Part 2) 2019
Zinc (Zn)	mg / l	ND	IS 3025 (Part 2) 2019
Lead (Pb)	mg / l	ND	IS 3025 (Part 2) 2019
Chromium (Cr)	mg / l	ND	IS 3025 (Part 2) 2019

-----End-----

For M/s: ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,



**Authorized Signatory**  
(Netra Pawar)

- Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
2. This report is not to be reproduced except in full, without written approval of the laboratory.

## Water Sample Analysis Report

<b>Report No - EAEPL/W/02/23/00278B</b>		<b>Report Date – 08.03.2023</b>	
<b>Name of Customer</b>	<b>M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"</b>		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Tanker Water	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/W/02/23/00278B (Near Site Office)	<b>Sample quantity and packing</b>	250ml X 1 No. St. PP Bottle
		<b>Preservation</b>	Cool -Transported and stored at 5°C (± 1°C).
<b>Date of Sampling</b>	28.02.2023	<b>Date of Receipt</b>	01.03.2023
<b>Sampling Procedure</b>	EAEPL/LAB/MB/SOP/17		
<b>Period of Analysis</b>	01.03.2023 to 03.03.2023		
<b>Report for the month</b>	February, 2023		


Discipline: Biological

Group: Water

Parameters	Unit	Results	Method
<b>Microbiological Analysis:</b>			
Coliforms	MPN/100ml	< 2	IS 1622:1981 Reaffirmed 2019
<i>E. coli</i>	MPN/100ml	< 2	IS 1622:1981 Reaffirmed 2019

-----End-----

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,



**Authorized Signatory**  
**(Shweta Sonawane)**

 Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
 2. This report is not to be reproduced except in full, without written approval of the laboratory.



## Soil Sample Analysis Report


<b>Report No - EAEPL/S/02/23/00278C</b>		<b>Report Date - 08.03.2023</b>	
<b>Name of Customer</b>	M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Soil	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/S/02/23/00278C (Near Centreside of Site)	<b>Sample quantity and packing</b>	500 g x 1 No. Ziplock Bag
		<b>Preservation</b>	Transported & stored in dry area
<b>Date of Sampling</b>	28.02.2023	<b>Date of Receipt</b>	01.03.2023
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/03		
<b>Period of Analysis</b>	01.03.2023 to 08.03.2023		
<b>Report for the month</b>	February, 2023		

**Discipline: Chemical**
**Group: Soil & Rock**

Parameters	Unit	Results	Methods
pH	-	7.82	IS 2720 (Part 26):1987, Reaffirmed:2021
Electrical Conductivity	µS/cm	438.80	IS 14767:2000, Reaffirmed:2021
Soil Moisture	%	13.76	IS 2720 (Part 02):1973 (Reaffirmed 2020) Oven dry method
Water Holding Capacity	%	32.16	EAEPL/LAB/SOP/SOIL/10
Total Kjeldhal Nitrogen	mg/kg	794.22	IS 14684:1999 Reaffirmed 2019
Organic Matter	%	1.29	IS 2720 (Part 22) – 1972 Reaffirmed 2020
Chlorides	mg/kg	99.70	EAEPL/LAB/SOP/SOIL/03
Calcium	mg/kg	2117.97	EPA 9080
Magnesium	mg/kg	106.24	EPA 9080
Sulphate	mg/kg	38.36	IS 2720 (Part 27):1977 Reaffirmed 2020
Available Phosphorus	mg/kg	1.78	EAEPL/LAB/SOP/SOIL/11
Sodium (Na)	mg/kg	2709.60	EPA 3050B
Potassium (K)	mg/kg	2284.13	EPA 3050B
<b>Heavy Metals:</b>			
Copper	mg/kg	158.55	EPA 3050B
Iron	mg/kg	91073.98	EPA 3050B
Lead	mg/kg	12.54	EPA 3050B
Zinc	mg/kg	120.03	EPA 3050B

-----End-----

For M/S. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,


 Authorized Signatory  
(Netra Pawar)

 Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
 2. This report is not to be reproduced except in full, without written approval of the laboratory.

## Ambient Noise Level Monitoring Report

<b>Report No - EAEPL/N/02/23/00278D</b>		<b>Report Date – 08.03.2023</b>	
<b>Name of Customer</b>	<b>M/s. Nirmal Lifestyle (India) Pvt. Ltd. " City of Joy"</b>		<b>Reference – WO #</b> RA/WO/007/2019 Dated 18.10.2019
<b>Site Address</b>	"City Of Joy" CTS No. 661/1/4, 661/1/5, 661/1/6, 661/1/7, 661/1/8, of village Mulund, Taluka Kurla, A.C.C Road in 'T' Ward, Mumbai.		
<b>Nature and Description of Sample</b>	Ambient Noise	<b>Sample Collected by</b>	EAEPL Laboratory
<b>Sampling locations and Sample Code</b>	EAEPL/N/02/23/00278D	<b>Sample quantity and packing</b>	Not Applicable
<b>Date of Sampling</b>	28.02.2023	<b>Date of Receipt</b>	Not Applicable
<b>Sampling Procedure</b>	EAEPL/LAB/SOP/04		
<b>Period of Analysis</b>	Not Applicable		
<b>Report for the month</b>	February, 2023		

Discipline: Chemical

Group: Atmospheric Pollution

Monitoring Locations	Units	Results		CPCB Norms	
		Day Time	Night Time	Day	Night
Near Main Gate of site	dB(A) Leq.	54.6	44.8	55	45
Near Centreside of site	dB(A) Leq.	53.4	43.9	55	45
Near Site Office	dB(A) Leq.	53.8	43.2	55	45
Near Backside of site	dB(A) Leq.	54.1	43.7	55	45

**Remark:** The noise level was observed to be within CPCB limits at all of the locations.

-----End-----

For M/s. ENVIRO ANALYSTS &amp; ENGINEERS PVT. LTD.,


  
**Authorized Signatory**  
 (Netra Pawar)

Note: 1. The result mentioned above refers only to the tested sample(s) and applicable parameter(s).  
 2. This report is not to be reproduced except in full, without written approval of the laboratory.



Government of Maharashtra

SEAC-2014/CR-438 /TC- 1  
Environment department  
Room No. 217, 2<sup>nd</sup> floor,  
Mantralaya Annexe,  
Mumbai- 400 032.  
Dated: 3<sup>rd</sup> September, 2014

To,  
M/s Nirmal Lifestyle (India) Pvt. Ltd  
Nirmal Ltd, Nirmal Mall,  
3rd Floor, Multiplex Building, L.B.S. Marg,  
Opp. Nirmal Nagar,  
Mulund (W), Mumbai 80.

**Subject: Environmental clearance for proposed "City of Joy" at village Mulund, Mumbai by M/s. Nirmal Lifestyle Pvt. Ltd.**

Sir,

This has reference to your communication on the above mentioned subject. The proposal was considered as per the EIA Notification - 2006, by the State Level Expert Appraisal Committee-II, Maharashtra in its 25<sup>th</sup> meeting and recommend the project for prior environmental clearance to SEIAA. Information submitted by you has been considered by State Level Environment Impact Assessment Authority in its 72<sup>nd</sup> meeting.

2. It is noted that the proposal is for grant of Environmental Clearance for proposed "City of Joy" at village Mulund, Mumbai. SEAC-II considered the project under screening category 8(a) B2 as per EIA Notification 2006.

**Brief Information of the project submitted by Project Proponent is as-**

SR. NO.	PREVIOUS EC DATED 26.05.2008	AMENDMENT PROPOSED
1	5A (Residential)	5B (Residential)
	P1+P2+St +20	P1+P2+St+20 Flr
	No. of Flats :80	No. of flats:78
2	6A (Residential)	6A (1 Basement+Extra 6 Floors)(Residential)
	P1+P2+ St + 30 Floors	B+ P1+P2+ Stilt+ 36Flr
	No. of Flats :104	32(Additional Flats)
		6B(Residential)
		B+ P1+P2+ Stilt+ 36Flr
		No. of Flats :136

	Office Building	9A (Residential)	9B (Residential)	9C (Residential)	9D (Residential)	9E (Residential)
	8 Podium+ St+14	B1+B2+ P1+P2+ STILT+ 40 Flr	B1+B2+ P1+P2+ STILT+ 40 Flr	B1+B2+ P1+P2+ STILT+ 21 Flr	B1+B2+ P1+P2+ STILT+ 21 Flr	B1+B2+ P1+P2+ STILT+ 21 Flr
3	No. of Flats : NIL	No. of flats:157	No. of flats:233	No. of flats:81	No. of flats:99	No. of flats:81
4	No. of flats:184	No. of flats:897				
Total No. of Flats : 1081						

Particulars	Sanctioned as per Previous EC	Proposed Expansion	Remarks	
FSI Area/TDR (m <sup>2</sup> )	1,52,710	56,793.76	--	
Fungible FSI Area (m <sup>2</sup> )	---	19877.81	--	
Non FSI Area (m <sup>2</sup> )	---	70871.73	Non FSI Area is Added for the following Buildings	
			Building No.	Configuration
			5B	P1+P2+STILT+20 FLOORS
			6A (6 Nos. Additional Floors Added & Basement Added)	B+P1+P2+STILT+36 FLOORS
			6B	B+P1+P2+STILT+36 FLOORS
			9A	B1+B2+P1+P2+STILT+40 FLOORS
			9B	B1+B2+P1+P2+STILT+40 FLOORS
			9C	B1+B2+P1+P2+STILT+21 FLOORS
			9D	B1+B2+P1+P2+STILT+21 FLOORS
9E	B1+B2+P1+P2+STILT+21 FLOORS			
Total Construction Area for the proposed Expansion(m <sup>2</sup> )		1,47,543.31		

DESCRIPTION	As per earlier EC obtained on 26 <sup>th</sup> May, 2008	Proposed Expansion /Amendment	Remarks,if any
Population	Commercial population:7440 Nos. Residential Population : 920 Nos.	Residential population : 4485 Nos.	Change of user from Commercial to Residential
WATER REQUIREMENT AND WASTE WATER MANAGEMENT (KLD)			
Total Water Requirement	1378	697	
Capacity of STP	455	660	
SOLID WASTE MANAGEMENT (Kg/day)			
Biodegradable Waste	2442	1622	
Non biodegradable Waste	2281	1081	
Total Solid Waste	4723	2703	
ELECTRICAL POWER			
Connected Load	31120 KW	24919 KW	
Maximum Demand	18718 KW	9307	

Name of the Project	The Proposed Residential Project "CITY OF JOY " at NEW C.T.S. Nos 661/1/4, 661/1/5, 661/1/6, 661/1/7 & 661/8 of Village Mulund (W), Mumbai – 400 080, Maharashtra.
Project Proponent	M/s Nirmal Lifestyle(India) Pvt. Ltd
Consultant	M/s. Enviro Analysts & Engineers Pvt. Ltd.
Accreditation of the consultant(NABET Accreditation)	QCI NABET LIST for the Construction Project/ Area Development Project/Township: S. No. 45 of list of consultant with provisional accreditation. (Rev.15/ December 5, 2013)
Type of Project	Residential Project
Location of the project	NEW C.T.S. Nos. 661/1/4, 661/1/5,661/1/6, 661/1/7 & 661/8 of Village Mulund (W), Mumbai – 400 080, Maharashtra.
Whether in Corporation/Municipal/Other area	Municipal Corporation of Greater Mumbai (MCGM)
Applicability of the DCR	MCGM DCR 1991

Note on the initiated work (if applicable)	Part construction has been carried out in accordance with the previous EC. Environmental Clearance under no.21-1007/2007-1A.III dated 26.05.2008 from Government of India- Ministry of Environment and Forests(I.A. Division)		
LOI/NOC from MHADA/ other approvals (If Applicable)	NA		
Total plot area	80371.92 m <sup>2</sup>		
Deductions	RG Area 10%- 8037.19 m <sup>2</sup>		
Net Plot Area	Net Plot Area- 72334.80 m <sup>2</sup>		
Permissible FSI (including TDR etc.)	1.0 + 0.33 + TDR+ Fungible FSI		
Proposed Built Up Area(FSI & Non FSI)	Sr. No	Particulars	Area(m <sup>2</sup> )
	1	FSI Area	56,793.77
	2	Fungible FSI Area	19,877.82
	3	Non FSI Area	70,871.73
	4	Total Construction Area	1,47,543.31
Ground Coverage Area (Percentage of plot not open to sky)	36,730.43 sq.mt , 45.70%		
Estimated Cost of the project	Rs.140 Crores		
Number of Buildings & configuration(s)	Building No.	Configuration	
	5B	P1+P2+STILT+20 FLOORS	
	6A (6 Nos. Additional Floors Added & Basement Added)	B+P1+P2+STILT+36 FLOORS	
	6B	B+P1+P2+STILT+36 FLOORS	
	9A	B1+B2+P1+P2+STILT+40 FLOORS	
	9B	B1+B2+P1+P2+STILT+40 FLOORS	
	9C	B1+B2+P1+P2+STILT+21 FLOORS	
	9D	B1+B2+P1+P2+STILT+21 FLOORS	
	9E	B1+B2+P1+P2+STILT+21 FLOORS	
Number of tenants and shops	Total no. of flats: 1081 Nos.(184 Nos. as per previous EC and 897 Nos. Proposed)		
Number of expected residents/users	4485 Residential users		
Tenement density per hectare	450 tenements/hectare		
Height of Building(s)	Building	Height	
	5B	68.35m	
	6 A and 6 B	116.55 m	
	9A and 9 B	137.20 m	
	9C,9D AND 9E	75.96 m	

Right of way (Width of the road from the nearest fire station to the proposed building(s))	24.70 m wide Jata Shankar Dosa Road & 13.40 m wide D.P. Road										
Turning radius for easy access of fire tender movement from all around the building excluding the width for the plantation	Minimum 6 m wide										
Existing Structure(s)	BLDG NO.1 & 1B(As per Previous EC) BLDG NO.3 & 4(As per previous EC) BLDG NO.7 & 8(As per Previous EC) BLDG NO.5A(As per Previous EC) BLDG NO.6A(Part Constructed As per previous EC)										
Details of the demolition with disposal (If applicable)	NA										
Total Water Requirement	Dry Season; Source : MCGM/Recycled										
	Particulars	Qty								Unit	
	Fresh Water	404								KLD	
	Recycled Water	600								KLD	
	Total Water Requirement	697								KLD	
	Swimming Pool make up	NIL								m3	
	Fire Fighting	300								m3	
	Wet Season; Source : MCGM/Recycled/RWH										
	Particulars	Qty								Unit	
	Fresh Water	404								KLD	
	Recycled Water	600								KLD	
	Total Water Requirement	606								KLD	
	Swimming Pool make up	NIL								m3	
	Fire Fighting	300								m3	
Rain Water Harvesting (RWH)	Level of Ground Water Table					2.7 m to 4 m					
	Size and Quantity of RWH tank(s)					1 x 176 m <sup>3</sup> , 1 x 70 m <sup>3</sup> , 1 x 60 m <sup>3</sup>					
	Location of the RWH tank(s)					Underground					
	Percolation Pits					Yes					
	Budgetary allocation (Capital cost and O&M cost)										
	Capital cost					Rs 76 Lakhs					
	O&M cost					Rs 0.5 Lakhs p.a					
UGT tanks	Location(s) of the UGT tank(s)- Lower Basement										
	Bldg	5B	6A	6B	9A	9B	9C	9D	9E	Total	
	UG(m3)	154	92	393	432	132	56	71	56	1352	
Strom water drainage	Natural water drainage pattern: NW to SE										
	Quantity of storm water:										
	Area					Quantity m <sup>3</sup> /s					

	Unpaved Area	0.0125	
	Paved Area	0.0062	
	RG Area	0.0167	
	Size of SWD: Internal drains of 450 wide x min. depth of 450 mm @ slope - 1 : 500		
Sewage & Waste Water	Sewage generation:	657 KLD	
	STP Technology	RMBR ( Rotating Media Bio Reactor )	
	Capacity of STP	660 KLD	
	Location of the STP	Ground Floor	
	Budgetary allocation (capital cost and O&M cost)		
	Capital Cost	Rs. 80 Lakhs	
	O & M Cost	Rs. 7 lakhs p.a	
Solid Waste Management	Waste generation in the Pre Construction and Construction phase :		
	Particulars	Quantity	Management
	Scrap Material (Steel/PVC/Aluminium)	148 tons	Entire scrap material generated will be sold for recycling.
	Aggregates	680 tons	Will be used in internal roads and bedding purpose.
	Wooden waste	16128 sqm	Will be recycled or sold.
	Tile/Marbles	6183 sqm	Will be used as china mosaic and skirting.
	Paint Cans	4945 nos	Will be sold to vendors.
	Glass	123 sqm	Will be sold to vendor for recycling.
	Waste generation in the operation phase:		
	Particulars	Quantity	Unit
	Dry waste (Kg/day):	1081	kg/day
	Wet waste (Kg/day):	1622	kg/day
	Total Waste	2703	kg/day
	E-waste	--	--
	Hazardous waste (Kg/month)	--	--
	Biomedical waste (Kg/month) (if applicable)	--	--
	STP sludge:20	20	kg/day
Mode of Disposal of Waste:			
Particulars	Management		
Dry waste	Will be managed through local recyclers.		
Wet Waste	Will be processed in the Organic Waste Converter and manure so obtained will be used for landscaping.		
E-Waste: NA	--		

	Hazardous Waste: NA	--
	Biomedical Waste: NA	--
	STP Sludge (Dry Sludge):	Will be processed in organic waste converter along with biodegradable waste.
	Area Requirement for OWC	161 sqmt
	Budgetary allocation (capital cost and O&M cost)	
	Capital Cost	Rs.22 lakhs
	O & M Cost	Rs.4 Lakhs pa
Green Belt Development	Total R.G. Area: 22,380.83 Sq.m (28%) RG area other than green belt (please specify for playground, etc.) RG area under green belt: RG on the podium (Sq. m): 22,380.83 Sq.m (28%) Number and list of trees species to be planted in the Podium RG:	
	List of trees	
	Botanical Names	Common Names
	<i>Cordia sebestena</i>	Scarlet cordia
	<i>Brownia coccinia</i>	Scarlet flame bean
	<i>Bismarkia nobilis</i>	Bismarck palm
	<i>Plumeria alba</i>	White frangipani
	<i>Plumeria rubra</i>	Red frangipani
	Total	220
	Botanical Names(Shrubs)	
<i>Alpina Zerembet</i> <i>Hiliconia</i> <i>Pandanus Dwarf</i>		
Number and list of trees species to be planted around the border of Nallah/Stream/Pond(if any): NIL Number, size, age and species of trees to be cut, trees to be transplanted: NA NOC for the tree cutting/transplantation/ compensatory plantation, if any: NA		
Budgetary allocation (Capital cost and O&M cost)		
Capital Cost	Rs 5 Lakhs	
O & M Cost	Rs. 2 Lakhs p.a	
Energy	Power Supply: Maximum Demand :9307 KW Connected Load :24,919 KW Source : MSEB DG set (Back up):1x250 KVA,1x625 and 1x1000 KVA Type of Fuel Used : HSD Energy saving by non-conventional method: Energy conservation measures: Energy efficient LED which give approx. 30% more light output for the same watts consumed and longer Lamp life. Assess the possibility of use of renewable energy. Use of solar	

lights for common area lighting.  
 Energy Efficient T5 and LED lamps are used in stilt, basement, common passages and refuges, club house podium area, façade and external lightning.  
 Maintaining the power factor between 0.95 lag and unity for common area loads.  
 Maintaining lighting power density as per ECBC standard in common areas and recreation facility.  
 The luminaries used for external building lights shall have lamps having minimum efficacy of 60lm/W.  
 Astronomical switching of outdoor lighting.  
 Proposing use of VFD's (Variable Frequency Drive) for all motors used in lifts, plumbing, Firefighting system.  
 Promoting use of star rated equipments such as AC, Fridge, Microwave, in houses by owners.  
 All the Common area Panels viz shall have electric metering to record, energy in Kwh, Demand in Kw.  
 Details calculations & % of saving:

**ENERGY SAVING SUMMARY FOR BUILDING NO 5B**

Sr.No	Items	Total Elect. Load Conventional case (Kw)	Elect. demand after using Energy saving means (kw)
	Energy Saving Parameters		
1	Stilt & Refuge area Ltg	6	3.7
2	External Area Ltg.	5	3.3
3	Common Area Ltg	6	3.5
4	Lifts with VFD & Regenerative Type	65	59
5	Plumbing System Load	19	17
	Total	100	86
<i>Overall Saving for the Project in %</i>			<i>14</i>
<i>Total Units saved based on Unit Consumption (Kw)</i>			<i>14</i>

**ENERGY SAVING SUMMARY FOR BUILDING NO 6**

Sr.No	Items	Total Elect. Load Conventional case (Kw)	Elect. demand after using Energy saving means (kw)
	Energy Saving Parameters		
1	Basement	25	17
2	Stilt, Podium & Refuge Floor	13.5	9
3	External Area Ltg.	8	5
4	Common Area Ltg	13	8
5	Lifts with VFD & Regenerative Type	200	180



6	Plumbing System Load	35	32
8	Basement Ventilation	150	135
9	Solar Lighting ( 40% of common area ltg)	8	0
	Total	453	385
<i>Overall Saving for the Project in %</i>			15
<i>Total Units saved based on Unit Consumption (Kw)</i>			68
<b>ENERGY SAVING SUMMARY FOR BUILDING NO 9</b>			
Sr.No	Items	Total Elect. Load Conventional case (Kw)	Elect. demand after using Energy saving means (kw)
	Energy Saving Parameters		
1	Basement	40	26
2	Stilt & Podium Floor	43	28
3	External Area Ltg.	10	7
4	Common Area Ltg	37	22
5	Lifts with VFD & Regenerative Type	548	493
6	Plumbing System Load	112	101
8	Basement Ventilation	500	450
9	Shaft Ventilation	100	90
10	Solar Lighting ( 40% of common area ltg)	24	0
	Total	1,414	1,217
<i>Overall Saving for the Project in %</i>			14
<i>Total Units saved based on Unit Consumption (Kw)</i>			197
Compliance of the ECBC guidelines: (Yes/No) (If yes then submit compliance in tabular form) –Yes			
Sr no.	Section no.	Requirement	Compliance met by
1	7.2.1.4	Exterior lighting control	Astronomical switching is considered for external & common area lighting
2	7.2.3	Exterior lighting luminaires	For lamps which operate at greater than 100 w, minimum efficacy of 60 lm/w lamps are proposed.
3	8.2.2	Energy efficient motors	Use of energy efficient motors and vfd's for pumps, lifts and ventilation fans.
4	8.2.3	Power factor correction	Maintaining power factor between 0.95 lag and unity at the point of correction.
5	8.2.4	Check-metering and monitoring	Load managers for emg. And utility loads.

	6	8.2.5.1	Power distribution power losses	A distribution loss not to exceed 1% of total power usage is met by adequately sizing the power cables.																							
	Budgetary allocation (capital cost and O&M cost)																										
	Capital Cost :			Rs.96.4 lakhs																							
	O& M Cost :			Rs. 4.82 lakhs																							
Environmental Management plan and Budgetary Allocation	Operation Phase (with Break-up)-																										
	<table border="1"> <thead> <tr> <th rowspan="2">Method Adopted</th> <th>Setting-up Cost</th> <th>Annual Maintenance and Operational Cost</th> </tr> <tr> <th>(Rs. in Lac)</th> <th>(Rs. in Lac per annum)</th> </tr> </thead> <tbody> <tr> <td>Rain Water Harvesting</td> <td>76</td> <td>0.5</td> </tr> <tr> <td>MSW</td> <td>22</td> <td>4</td> </tr> <tr> <td>STP</td> <td>80</td> <td>7</td> </tr> <tr> <td>Energy Efficient System</td> <td>96.4</td> <td>4.82</td> </tr> <tr> <td>Landscaping</td> <td>5</td> <td>2</td> </tr> <tr> <td><b>TOTAL</b></td> <td><b>279.4</b></td> <td><b>18.32</b></td> </tr> </tbody> </table>				Method Adopted	Setting-up Cost	Annual Maintenance and Operational Cost	(Rs. in Lac)	(Rs. in Lac per annum)	Rain Water Harvesting	76	0.5	MSW	22	4	STP	80	7	Energy Efficient System	96.4	4.82	Landscaping	5	2	<b>TOTAL</b>	<b>279.4</b>	<b>18.32</b>
	Method Adopted	Setting-up Cost	Annual Maintenance and Operational Cost																								
		(Rs. in Lac)	(Rs. in Lac per annum)																								
	Rain Water Harvesting	76	0.5																								
	MSW	22	4																								
	STP	80	7																								
	Energy Efficient System	96.4	4.82																								
Landscaping	5	2																									
<b>TOTAL</b>	<b>279.4</b>	<b>18.32</b>																									
<p>Quantum and generation of Corpus fund and commitment:  After occupancy, Co-Op societies will be formed.  The Operation and Maintenance of Environmental Management Facilities (EMF) shall be taken care by the developers till the society is formed.  Afterwards, EMF shall be handed over to Society.</p>																											
Traffic Management	<p>Nos. of the junction to the main road &amp; design of confluence:  Entries &amp; Exits :  6 Entries/Exits: One from 24.7 m wide Jata Shankar Dosa Road(E) and five from 13.4 m wide DP Road (N)  Roads:  24.7 m wide Jata Shankar Dosa Road(E)  13.4 m wide DP Road connected to 24.70 m wide Jata Shankar Road  Parking Details: 1038 Four wheeler Parking  Area and nos. of the Basements: 2 Basements (18641.09 m<sup>2</sup> )  Area and nos. of Podia: 2 Podia (15454.03 m<sup>2</sup>)  Stilt Area : 4975.05 m<sup>2</sup>  Total Area=33,550 m<sup>2</sup>  Area/Car =32.32 m<sup>2</sup>  Public Transport: Not applicable  Width of all Internal roads :All internal Roads of minimum 6m width</p>																										

3. The proposal has been considered by SEIAA in its 72<sup>nd</sup> meeting & decided to accord environmental clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implementation of the following terms and conditions :

- (i) This environment clearance is issued subject to restricting total no of new flats to be constructed up to 738 as approved by the local authority. PP may approach to SEIAA as and when local authority approves the proposed new flats.
- (ii) This environmental clearance is issued subject to land use verification. Local authority / planning authority should ensure this with respect to Rules, Regulations, Notifications, Government Resolutions, Circulars, etc. issued if any. Judgments/orders issued by Hon'ble High Court, Hon'ble NGT, Hon'ble Supreme Court regarding DCR provisions, environmental issues applicable in this matter should be verified. PP should submit exactly the same plans appraised by concern SEAC and SEIAA. If any discrepancy found in the plans submitted or details provided in the above para may be reported to environment department. This environmental clearance issued with respect to the environmental consideration and it does not mean that State Level Impact Assessment Authority (SEIAA) approved the proposed land use.
- (iii) This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
- (iv) PP has to abide by the conditions stipulated by SEAC & SEIAA.
- (v) The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.
- (vi) "Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- (vii) All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
- (viii) Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.
- (ix) Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche and First Aid Room etc.
- (x) Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- (xi) The solid waste generated should be properly collected and segregated. dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material

- (xii) Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.
- (xiii) Arrangement shall be made that waste water and storm water do not get mixed.
- (xiv) All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- (xv) Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- (xvi) Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- (xvii) Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- (xviii) Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- (xix) Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.
- (xx) Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- (xxi) The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- (xxii) The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.
- (xxiii) Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- (xxiv) Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- (xxv) Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).
- (xxvi) Ready mixed concrete must be used in building construction.
- (xxvii) The approval of competent authority shall be obtained for structural safety of the buildings due to any possible earthquake, adequacy of fire fighting equipments etc. as per National Building Code including measures from lighting.
- (xxviii) Storm water control and its re-use as per CGWB and BIS standards for various applications.


- (xxix) Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- (xxx) The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- (xxxi) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated effluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.
- (xxxii) Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.
- (xxxiii) Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.
- (xxxiv) Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.
- (xxxv) Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- (xxxvi) Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
- (xxxvii) Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement
- (xxxviii) Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non conventional energy source as source of energy.
- (xxxix) Diesel power generating sets proposed as source of back up power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.

- (xl) Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
- (xli) Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- (xlii) Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspirational for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement
- (xliii) The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.
- (xliv) Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.
- (xlv) Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
- (xlvi) Six monthly monitoring reports should be submitted to the Regional office MoEF, Bhopal with copy to this department and MPCB.
- (xlvii) A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.
- (xlviii) In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.
- (xlix) A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
- (l) Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.
- (li) The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at <http://ec.maharashtra.gov.in>.
- (lii) Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1<sup>st</sup> June & 1<sup>st</sup> December of each calendar year.

- (liii) A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
  - (liv) The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO<sub>2</sub>, NO<sub>x</sub> (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
  - (lv) The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
  - (lvi) The environmental statement for each financial year ending 31<sup>st</sup> March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
  5. In case of submission of false document and non compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environmental Clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
  6. The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.
  7. **Validity of Environment Clearance:** The environmental clearance accorded shall be valid for a period of 5 years.
  8. In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.
  9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution ) Act, 1981,

the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling ) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.

10. Any appeal against this environmental clearance shall lie with the National Green Tribunal , Van Vigyan Bhawan, Sec- 5, R.K. Puram, New Dehli – 110 022, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

  
(Medha Gadgil)  
Additional Chief Secretary,  
Environment department &  
MS, SEIAA

**Copy to:**

1. Shri. R. C. Joshi, IAS (Retd.), Chairman, SEIAA, Flat No. 26, Belvedere, Bhulabhai desai road, Breach candy, Mumbai- 400026.
2. Shri. Ravi Bhushan Budhiraja, Chairman, SEAC-II, 5-South, Dilwara Apartment, Cooperage, M.K.Road, Mumbai 400021
3. Additional Secretary, MOEF, 'Paryavaran Bhawan' CGO Complex, Lodhi Road, New Delhi – 110510
4. Member Secretary, Maharashtra Pollution Control Board, with request to display a copy of the clearance.
5. The CCF, Regional Office, Ministry of Environment and Forest (Regional Office, Western Region, Kendriya Paryavaran Bhavan, Link Road No- 3, E-5, Ravi-Shankar Nagar, Bhopal- 462 016). (MP).
6. Regional Office, MPCB, Mumbai.
7. Collector, Mumbai
8. Commissioner, Municipal Corporation Greater Mumbai (MCGM)
9. IA- Division, Monitoring Cell, MoEF & CC, Indira Paryavaran Bhavan, Jorbagh Road, Aliganj, New Delhi-110003.
10. Select file (TC-3)

(EC uploaded on 9/9/2014 )



By Speed Post

No. 21- 1007/2007-IA .III  
 Government of India  
 Ministry of Environment and Forests  
 (I.A. Division)

Paryavaran Bhawan,  
 CGO Complex, Lodhi Road  
 New Delhi 110510  
 Dated: May 26, 2008

To

M/s. Nirmal Lifestyle (India) Pvt. Ltd.  
 LBS Road,  
 Near Old Hext Pharamceutical Company  
 Opp. Nirmal Complex,  
 Mulund, Mumbai- 400 080  
 Maharashtra

**Subject: Environmental Clearance for proposed project "City of Joy" at CTS Nos. 661/14 & 661/15(pt) and Village Mulund (W), Mumbai, Maharashtra.**

Dear Sirs,

I am directed to refer to your application seeking prior environmental clearance for the above project under the EIA Notification 2006. The above proposal has been appraised as per prescribed procedure on the basis of the mandatory documents enclosed with the application viz. the Form 1, Form 1A and the additional clarifications furnished in response to the observations of the Expert Appraisal Committee (EAC) constituted by the competent authority in its 29<sup>th</sup> meeting held on April 25-26, 2008.

2. The project proponent is proposing for construction of "City of Joy" at CTS Nos. 661/14 & 661/15(pt) and New CTS No. 661/1/7 of Village Mulund (W), Mumbai, Maharashtra at a cost of Rs. 245 crore. The project involves construction of residential and office buildings as per details given below:

	Component	Wing 1	Wing 2	No. of Flats
1.	<b>Residential</b>			
	Bldg. No. 1	P1+ P2+St+20	-	80
	Bldg. No. 2	P1+P2+St+30	-	104
2.	<b>Office building</b>	P1+P2+P3+P4+P5+P6 +P7+P8+St+14		-

The total plot area is 80371.9 sq. m. Total built up area as per FSI is 1,52,710.0 sq. m. Total water requirement will be 1197 cu.m/day including recycled water and 413 cu.m/day of waste water will be generated from the buildings which will be treated in two sewage treatment plant with capacities of



125 cu.m/day and 330 cu.m/day respectively. The treated wastewater will be used for flushing, and Horticulture purpose and unused waste water will be discharged in to municipal sewer. The solid waste generated from the buildings will be 4722 Kg/day. The solid waste will be segregated in to dry and wet waste. The recyclable/dry solid waste will be handed over to authorized vendors for recovery of recyclable material and wet garbage will be disposed of organic waste converter. The parking space is proposed for parking of 1910 cars.

3. The EAC after due consideration of the relevant documents submitted by the project proponent and additional clarifications furnished in response to its observations have recommended the grant of environmental clearance for the project mentioned above subject to compliance with the EMP and other stipulated conditions. Accordingly, the Ministry hereby accords necessary environmental clearance for the project under category 8 (b) of EIA Notification 2006 subject to the strict compliance with the specific and general conditions mentioned below:

## PART A- SPECIFIC CONDITIONS

### I. Construction Phase

- i. Vehicles hired for construction activities should be operated only during non-peak hours.
- ii. All the top soil excavated during construction activities should be stored for use in horticulture/landscape developments within the project site.
- iii. Ready mixed concrete shall be used in building construction.
- iv. Water demand during construction shall be reduced by use of pre mixed concrete, curing agents and other best practices.
- v. Permission to draw and use ground water for construction work shall be obtained from competent authority prior to construction/operation of the project.
- vi. Fixtures for showers, toilet, flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- vii. Use of glass may be reduced upto 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
- viii. Roof should meet the prescriptive requirement as per energy conservation building code by using appropriate thermal insulation material to fulfill requirement.
- ix. Opaque wall should meet prescriptive requirement as per energy conservation building code which is proposed to be mandatory for all air conditioned spaces while it is aspirational for non air conditioned spaces by use of appropriate thermal insulation to fulfill requirement.
- x. Storm water control and its reuse should be as per Central Ground Water Board and BIS standards for various applications.
- xi. All required sanitary and hygienic measures including portable toilets/septic tank etc. for labour should be in place before starting



- construction activities and to be maintained throughout the construction phase.
- xii. Soil and ground water samples will be tested to ascertain that there is no threat to groundwater quality by leaching of heavy metals and other toxic contaminants.
  - xiii. A First Aid Room will be provided at the project site both during construction and operation of the project.
  - xiv. Adequate drinking water facility should be provided for construction workers at the site. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
  - xv. Disposal of muck including excavated material during construction phase should not create any adverse effects on the neighboring communities and be disposed off taking the necessary precautions for general safety and health aspects of people.
  - xvi. Diesel power generating sets used during construction phase should be of "enclosed type" to prevent noise and should conform to rules made under Environment (Protection) Act 1986, prescribed for air and noise emission standards.
  - xvii. Ambient noise levels should conform to standards both during day and night when measured at boundary wall of the premises. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase.
  - xviii. The construction agencies shall use flyash based material/ products as per the provisions of fly ash notification of 14.9.1999 and as amended on 27.8.2003.
  - xix. Vehicles hired for bringing construction material at site should be in good condition and should have valid "pollution under check"(PUC) certificate and to conform to applicable air and noise emission standards and should be operated only during non-peaking hours.
  - xx. Construction spoils including bituminous material and other hazardous materials must not be allowed to contaminate water courses and the dump sites for such material must be secured so that they should not leach into the ground water.
  - xxi. Any hazardous waste generated during construction phase should be disposed of as per applicable Rules & norms with necessary approvals of the State Pollution Control Board.
  - xxii. Under the provisions of the Environment (Protection) Act 1986, legal action shall be initiated against the project proponent if it was found that construction of the project had started without obtaining environmental clearance.
  - xxiii. The diesel required for operating DG Set shall be stored in underground tanks and if required, clearance from the Chief Controller of Explosives shall be taken.
  - xxiv. The approval of competent authority shall be obtained for structural safety of the buildings due to any possible earthquake, adequacy of fire fighting equipments etc. as per National Building Code including protection measures from lightening etc.



- xxv. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase so as to avoid disturbance to the surroundings.

## II. Operation Phase

The environmental clearance recommended to the project is subject to the specific conditions as follows:

- i. Diesel power generating sets proposed as source of back up power for lifts and common area illumination should be of "enclosed type" and conform to rules made under The Environment (Protection) Act 1986. The location of DG Set may be decided in consultation with State Pollution Control Board.
- ii. During night time the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
- iii. Noise should be controlled to ensure that it does not exceed the prescribed standards.
- iv. Weep holes in the compound walls shall be provided to ensure natural drainage of rainwater in the catchment area during the monsoon period.
- v. The STP shall be installed for the treatment of sewage generated to the prescribed standards including odour and treated effluent will be re-cycled to the maximum extent possible. In case treated effluent is to be discharged separately during monsoon period consent of State Pollution Control Board shall be taken.
- vi. Separation of gray and black water should be done by the use of dual plumbing line. Treatment of 100% gray water by decentralized treatment should be done.
- vii. For disinfection of waste water ultra violet radiation shall be used in place of chlorination.
- viii. Rainwater harvesting and ground water recharging shall be practiced. Oil & Grease trap shall be provided to remove oil and grease from the surface run off and suspended matter shall be removed in a settling tank before its utilization for rainwater harvesting.
- ix. The solid waste generated should be properly collected & segregated. Wet garbage should be composted and dry/inert solid waste should be disposed off to approved sites for land filling after recovering recyclable material.
- x. The open spaces inside the plot should be preferably landscaped and covered with vegetation of indigenous variety. Green belt of adequate width and density will be provided all around the periphery of the plot preferably with local species to reduce noise and dust level.
- xi. The ground water levels and its quality should be monitored regularly in consultation with Central Ground Water Authority.
- xii. A Report on the energy conservation measures should be prepared incorporating details about building materials & technology, R & U Factors etc and submitted to the Ministry in three months time.



- xiii. The values of R & U for the building envelope should meet the requirements of the hot & humid climatic location. Details of the building envelope should be worked out and furnished in three months time.
- xiv. Energy conservation measures like installation of CFLs/FLs for lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Used CFLs & FLs should be properly collected and disposed of/sent for recycling as per the prevailing rules/ guidelines/ standards issued by the regulatory authority to avoid Mercury contamination. Use of solar panels may be done to the extent possible.
- xv. The buildings should have adequate distance between them to allow movement of fresh air and passage of light to the premises.
- xvi. Adequate measures should be taken to prevent odour problem from solid waste processing plant as also from STP.

#### **PART – B. GENERAL CONDITIONS**

- i) The environmental safeguards contained in the documents should be implemented in letter and spirit.
  - ii) Provision should be made for the supply of kerosene or cooking gas and pressure cooker to the laborers during construction phase.
  - iii) 6 monthly monitoring reports should be submitted to the Ministry and its Regional Office.
4. Officials from the Regional Office of MOEF, Bhopal who would be monitoring the implementation of environmental safeguards should be given full cooperation, facilities and documents / data by the project proponents during their inspection. A complete set of all the documents submitted to MoEF should be forwarded to the CCF, Regional office of MOEF, Bhopal.
5. In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Ministry.
6. The Ministry reserves the right to modify/add additional environmental safeguards subsequently, if found necessary. Environment Clearance granted will be revoked if it is found that false information has been given for approval of the project.
7. Necessary permission shall be obtained from the State Fire Department for providing fire safety measures before allotment of premises. If any forest land is involved in the proposed site, clearance under the Forest Conservation Act, 1980 from the Competent Authority shall be taken.
8. These stipulations would be enforced among others under the provisions of the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and control of Pollution) act 1981, the Environment (Protection) Act, 1986 and the Public Liability (Insurance) Act, 1991.



9. The project proponent shall enter in to MOU with all buyers of the property to ensure operation and maintenance of the STP and other assets.

10. Any appeal against this environmental clearance shall lie with the National Environment Appellate Authority, if preferred, within a period of 30 days as prescribed under section 11 of the National Environment Appellate Act, 1997.

*K.C. Rathore*  
(K.C. RATHORE)  
Additional Director (IA)

Copy to: -

1. The Secretary, Department of Environment, Government of Maharashtra, New Administrative Building, 15<sup>th</sup> Floor, Opp. Mantralaya, Mumbai.
2. The Chairman, State Environment Impact Assessment Authority, Department of Environment, Government of Maharashtra, New Administrative Building, 15<sup>th</sup> Floor, Opp. Mantralaya, Mumbai.
3. The Member Secretary, Maharashtra State Pollution Control Board, Kalptaru Point, 3<sup>rd</sup> Floor, Near Sion Circle Opp. Cine Planet Cinema, Sion(E), Mumbai.
4. The CCF, Regional Office, Ministry of Environment & Forests, Bhopal.
5. IA - Division, MOEF, New Delhi - 110001.
6. Guard file.

(K.C. RATHORE)  
Additional Director (IA)































